

Australian Institute for the **Certification** of Inspection Personnel

APEK GUIDANCE NOTE

## ACCEPTANCE OF NON-CONFORMING WELD ROOT OVERLAP, REINFORCEMENT, SPATTER IN CS PE

Developed for: ACA, AICIP, AIE, AIES, AINDT, APIA, CAAA, EA, ME Aust, NATA, Standards Aust, WTIA, PE Industry & Regulators

## 1 **Scope** Shows and assesses 4 significant signs or indications (Fig 1) detected during in-service inspection of PE

Gives basis for acceptance of these flaws and non-conforming weld root overlap




Fig 1 Internal View (4 types of flaw)

Feedback for all, including trainees; show that some DNCs can be accepted; & 2 Purpose support AS/NZS 3788 3 PE involved New vertical air-oil separator: Carbon steel, Class 3 pressure vessel 9mm thick, 700mm OD. Imported ASME VIII-1, n=70% ie no RT or UT, P = 2MPa, Hydrotest = 1.3P, T = 60C, Hazard Level = C 4 Signs Root reinforcement: 2.5mm continuous; root overlap: 2mm - continuous on both sides: minor spatter from circumferential weld; and weld oxide scale (Indications) 5 Sign location Inside vessel on vertical longitudinal weld. Detection By IS Inspector during commissioning inspection in Australia by VT in 2014 6 .1 The inspector sought competent advice on flaw identification etc, and which 7 Assessment Standard applied. (by inspector, .2 Check with 100% UT showed no other flaws. Various Standards were reviewed. .3 Overlap did not conform (DNC) with AS 4037, but was acceptable in ASME VIII-1 adviser and UW35a). owner-user) Overlap is equivalent to a joint joggled or with backing strip - both allowed for circumferential joints. Overlap (and spatter and oxide scale) might not be acceptable for severe corrosion service or where hygiene is critical as with food or medical PE. .4 For this Service conditions: Corrosion negligible with oil - very low risk of corrosion failure. Low stress (effective safety factor =  $3.5/(\eta=70\%) = 5.0$ ; low stress range, medium no. of cycles and "crack" parallel to stress. Hence very low risk of fatigue failure. Spatter and thin oxide scale acceptable. .5 Weld root reinforcement of 2.5 mm complies with AS 4037, is within 0.1mm with ASME VIII-1. It might not be acceptable for flow-accelerated corrosion or complete drainage During manufacture 2013 overseas 8 Occurrence Root overlap is rare - some inspectors did not recognise 9 Failure modes Corrosion and fatigue possible - very low probability

Fig 2 Joint during welding

9mm

damage mechanism



10 Probable cause(s)	Poor fitting backing bar (eg copper) for small diameter vessel	
11 Outcome	Put into service without removal or repair because: a) Conformance with ASME b) For this application – corrosion and fatigue failure are very unlikely c) Owner-user happy as PE was urgently needed at minimum cost	
12 <b>Fix</b>	No correction was required.	
13 <b>Prevention</b> inspection.	In manufacture: better shaped backing bar, edge bending or clamping; better Q	≀A or
desirable	In service: after 10 to 15 years, spot UT of the vertical weld lower half might be	
14 Lesson(s)	<ul> <li>.1 If a flaw is judged DNC, consider if PE might be fit for service and if an assessment is worthwhile.</li> <li>.2 Different laws, Standards or service may have different acceptance criteria eg 8.3 &amp; .5.</li> <li>.3 Acceptance of DNCs requires proper assessment, justification, documentation and sign-off.</li> </ul>	
15 References	AS/NZS 3788 PE In-service inspection AS 4037 PE Examination and testing ASME BPV Code Sect. VIII Pressure vessels Div 1 SA	A,NY